
PAVING, DRAINAGE AND UTILITY IMPROVEMENTS

FOR

ATELIER TOWER
BLOCK 528, TRACT II

2121 FLORA STREET DALLAS, TEXAS 75201

311T-8854



OWNER / DEVELOPER

ZOM TEXAS, INC. 3400 CARLISLE STREET, SUITE 500 DALLAS, TEXAS 75204 DAVID KUBIN dtk@zomusa.com

CIVIL


HALFF ASSOCIATES, INC. 1201 N. BOWSER ROAD RICHARDSON TEXAS 75081 214.346.6200 DAVID LITTLETON, P.E. dlittleton@halff.com



TBPE FIRM# F-312

	SHEET INDEX	55,40,0,1	25.40.01
SHEET#	SHEET NAME	REVISION (11-14-2016)	REVISION (07-28-2017)
	COVER SHEET	RTF1	RTF2
C0.01	GENERAL NOTES		RTF2
1 of 2	ALTA/ACSM LAND TITLE SURVEY		
2 of 2	ALTA/ACSM LAND TITLE SURVEY		
C1.01	SURVEY CONTROL PLAN		
C1.02	EXISTING ELEVATIONS AND DEMOLITION PLAN	RTF1	RTF2
C2.01	OVERALL PAVING PLAN	RTF1	RTF2
C2.02	PEARL ST. PAVING PLAN	RTF1	RTF2
C2.03	OLIVE ST. PAVING PLAN	RTF1	RTF2
C2.04	FLORA ST. PAVING PLAN	RTF1	RTF2
C3.01	GRADING PLAN	RTF1	RTF2
C4.01	EXISTING DRAINAGE AREA MAP		
C4.02	PROPOSED DRAINAGE AREA MAP		RTF2
C4.03	STORM DRAINAGE PLAN & PROFILE	RTF1	RTF2
C4.04	STORM DRAINAGE PLAN & PROFILE	RTF1	RTF2
C5.01	WWTR RELOCATION		
C5.02	UTILITY PROFILES		
C6.01	EROSION CONTROL PLAN	RTF1	RTF2
C6.02	EROSION CONTROL NOTES & DETAILS		

CITY OF DALLAS REFERENCE SHEET INDEX					
SHEET #	SHEET NAME				
351D-390, SH.10	PERIMETER DRAINAGE AREA MAP				
311D-3133, SH.26	DRAINAGE PLAN				
311D-3133, SH.44	CORNER PLAN ENLARGEMENT				
311D-3133, SH.59	PAVEMENT DETAILS				
311D-3133, SH.60	PAVEMENT DETAILS				



REVISION TABLE						
NUMBER	DATE					
1	Site plan changes	11/14/2016				
2	Mobility and Street Services comments	07/28/2017				

CITY OF DALLAS 311T-8854

GENERAL NOTES:

- 1. Contractor is responsible for, and must obtain prior to construction, all necessary construction permits required by the City of Dallas.
- 2. All construction shall conform to the requirements of the City of Dallas and shall be in accordance with the standard specifications of this project, and the Fourth Edition of the "Standard Specifications for Public Works Construction - North Central Texas" herein referred to as "COG" specifications, as amended by the applicable portions of the City of Dallas Department of Public Works Addendum to North Central Texas Standard Specifications for Public Works Construction (October, 2011). Copies may be obtained from the North Central Texas Council of Governments, 616 Six Flags Drive, Suite 200, Arlington, Texas 76005-5888. (817) 640-330 and TXDOT 2004 Specifications for Construction and Maintenance of Highways, Streets and Bridges.
- 3. All street cut repairs shall conform to the City of Dallas Pavement Cut and Repair Standards Manual, Department of Public Works and Transportation, dated October 2003.
- City of Dallas Department of Public Works Standard Construction Details (File 251D-1) referenced within these plans can be found on the City of Dallas website (http://www.dallascityhall.com/pwt/pdf/standards 251D-1 signatures.pdf)
- The Contractor shall abide by all applicable federal, state, and local laws governing excavation. The Contractor shall provide detailed plans and specifications for trench safety systems that comply with applicable laws governing excavation. These plans shall be sealed by an Engineer experienced in the design of trench safety systems and licensed by the State of Texas. Submit plan to the Owner prior to commencing work. The Contractor shall be solely responsible for all aspects of work related to excavation.
- Existing utility locations shown are taken from available records provided by the utility Owner and field locations of surface appurtenances. Locations shown are generally schematic in nature and may not accurately reflect the size and location of each particular utility. Some utility lines may not be shown. Contractor shall assume responsibility for actual field location and protection of existing facilities whether shown or not. Contractor shall also assume responsibility for repairs to existing facilities, whether shown or not, damaged by contractor's activities. Differences in horizontal or vertical location of existing utilities shall not be a basis for additional expense.
- Contractor shall locate and adjust existing utility manhole lids, cleanouts, water valves and other surface appurtenances as required for new construction. Contractor shall coordinate utility adjustments with other disciplines and the appropriate utility agencies and provide for all fees for permits, connections, inspections, etc. These adjustments shall be considered incidental to the construction contract.
- The Contractor shall protect existing property monumentation and primary control. Any such points which the Contractor believes will be destroyed shall have offset points established by the Contractor prior to construction. Any monumentation destroyed by the Contractor shall be reestablished at his expense.
- Barricading and traffic control during construction shall be the responsibility of the Contractor and shall conform to the latest edition of the "Texas Manual on Uniform Traffic Control Devices", Part VI in particular. Traffic flow and access shall be maintained during all phases of the construction. The Contractor is responsible for providing traffic safety measures for work on project.
- 10. Onsite planimetric and topographic mapping, and boundary data taken from survey performed by Halff Associates, Inc, dated March 2013. Offsite planimetric and topographic information taken from survey performed by Halff Associates, Inc., dated May 2015. SUE mapping data taken from survey performed by Halff Associates, Inc. dated May 2015.
- 11. Any damages that may occur to real property or existing improvements shall be restored by the Contractor to at least the same condition that the real property or existing improvements were in prior to the damages. This restoration shall be subject to the Owner's approval; moreover, this restoration shall not be a basis for additional compensation to the Contractor. Restoration shall include, but not be limited to, regrassing, revegetation, replacing fences, replacing trees, etc.
- 12. It shall be the responsibility of the Contractor to:
 - Prevent any damage to private property and property owner's poles, fences, shrubs, etc.
 - B. Provide access to all drives during construction.
 - C. Protect all underground utilities to remain in service.
 - D. Notify all utility companies and verify location of all utilities prior to start of construction.
- 13. Contractor shall maintain positive drainage at all time during construction. Ponding of water in streets, drives, truck courts, trenches, etc. will not be allowed.
- 14. Contractor shall maintain existing sanitary sewer and water service at all times during construction.
- 15. Contractor is responsible for coordination with utility companies and adjustment of existing sanitary sewer cleanouts, water meters and any other appurtenances to new grade as required.
- 16. Pavement removal and repair shall conform to the City of Dallas requirements. All sawcuts shall be full depth cuts. Contractor shall make efforts to protect concrete and/or asphalt edges. Any large spalled or broken edges shall be removed by sawcutting pavement prior to replacement.

EROSION CONTROL NOTES:

1. Refer to the Erosion Control Sheets, sheets C6.01 and C6.02 for Erosion Control notes.

DEMOLITION NOTES:

- 1. For additional extents for demolition, refer to grading, storm drainage, paving, and dimension control, water and
- 2. Information provided on this plan does not delineate any underground foundation or objects that currently may be
- The contractor shall be responsible for proper removal and disposal of materials as required by the Owner or Owner's representative.

GRADING NOTES:

- 1. No grading or earthwork shall commence until filing of a Notice of Intent to the Texas Commission of Environmental Quality (TCEQ) if applicable and Implementation of the Storm water Pollution Prevention Plan by the Contractor. A site erosion control plan and stormwater pollution prevention plan shall be prepared and provided to the City of Dallas by others prior to start of construction.
- 2. The existing ground surface shall be stripped of vegetation, roots, old construction debris, and other organic materials. Material unsuitable for fill shall be removed from the site and properly disposed of.
- 3. The subgrade should be firm and able to support the construction equipment without displacement. Soft or yielding subgrade should be corrected and made stable before construction proceeds. The subgrade shall be proof rolled using a heavy pneumatic tire roller, loaded dump truck or similar piece of heavy equipment.
- All areas to receive fill shall be stripped of vegetation and the top six (6) inches scarified prior to receiving any fill. Fill material shall be placed in loose lifts not exceeding 8-inches in uncompacted thickness. The fill material shall be uniform with respect to material type and moisture content. Clods and chunks of material shall be broken down and the fill material mixed by disking, blading, or plowing, as necessary, so that a material of uniform moisture and density is obtained for each lift. Water required to bring the fill material to the proper moisture content should be sprinkled evenly through each layer.
- The fill material shall be compacted between to at least 95 percent of the maximum dry density as determined by the Standard Proctor test, ASTM D 698. In conjunction with the compacting operation, the fill material shall be brought to the proper moisture content. The moisture content of the compacted soils should be maintained between -2 and +2 percent of the optimum value (determined from ASTM D 698). Refer to the Project Geotechnical Report.
- The Contractor shall administer sprinklers for dust control, earthwork or base construction as required or as directed by the Engineer in accordance with the TXDOT Standard Specification for Construction, Item 204-Sprinklering.
- 7. Contractor's work shall include pavement removal and disposal required for new walk, drive, curb, gutter and other grading features. Contractor shall be responsible for all coordination, inspection and testing required by the Owner and/or the City of Dallas.
- All sidewalks shall maintain 2% cross slope maximum. Longitudinal slopes along sidewalks and accessible routes shall not exceed 5% in the direction of travel. Slopes within designated handicap parking or loading areas shall not exceed 2% in any direction.
- 9. Site grading and pavement subgrade shall be prepared in accordance with the Geotechnical Report No.19:6529 prepared by ECS Texas, LLP. dated April 24, 2015.
- 10. Proposed spot elevations represent gutter elevation unless noted otherwise.

STORM DRIANAGE NOTES:

GENERAL:

- A) All construction shall conform to the requirements of the City of Dallas and shall be in accordance with the standard specifications of this project, and the Fourth Edition of the "Standard Specifications for Public Works Construction - North Central Texas" herein referred to as "COG" specifications. Copies may be obtained from the North Central Texas Council of Governments, 616 Six Flags Drive, Suite 200, Arlington, Texas 76005-5888. (817) 640-3300.
- B) All RCP wyes and bends shall be prefabricated by the pipe manufacturer.
- C) Construct concrete collar at all pipe size change locations.

2. CLOSED CONDUITS:

- A) Closed conduits shall be installed per COG Item 508 specifications.
- B) Only Reinforced Concrete Pipe (RCP) is approved for use.
- Class IV RCP shall be used where the pipe cover is greater than 1 foot and less than 3 feet. Class III RCP shall be used when the pipe cover is from 2 feet to 6 feet. The Class of all other RCP shall be determined by an Engineer per Loads and Supporting Strengths, American Concrete Pipe Association.

 D) For pipes, embedment shall be Class B per COG Item 504.5.2.3.
- E) The contractor shall seal all joints on closed conduits with Omni-Flex joint seals, or equal; unless
- approved otherwise by the engineer. F) The minimum size for laterals is 18 inches in diameter. The minimum size for mains is 24 inches in diameter
- 3. CONCRETE FOR PRE-CAST PRODUCTS:
 - A) All concrete to be used in pre-cast products for drainage structures shall come from plants certified by the National Pre-cast Concrete Association.

4. CONCRETE:

- A) Concrete shall be made with a minimum of 5 sacks of cement and have a minimum compressive
- strength of 3,000 PSI at 28 days, unless noted otherwise. B) All reinforcing steel shall be new, neat, billet-steel per ASTM designation A-615, Grade 60, and shall be detailed and placed for ACI Manuals SP-88 and 318, latest additions. All reinforcing steel shall have minimum 15 inch lap splices, unless noted otherwise on the plans.
- C) The Contractor shall use a liquid membrane-forming curing compound per COG Item 303.2.13.1.1. D) All exposed surfaces shall have 3/4 -inch chamfer.
- 5. TESTING:
 - All closed conduits shall be Television Inspected per City of Dallas specifications.

PAVING NOTES:

- Pavement removal and repair shall conform to City of Dallas requirements. All sawcuts shall be full depth cuts. Contractor shall make efforts to protect concrete and/or asphalt edges. Any large spalled or broken edges shall be removed by sawcutting pavement prior to replacement.
- Contractor's work shall include pavement removal and disposal required for new walk, drive, curb, gutter and other paving features. Contractor shall be responsible for all coordination, inspection and testing required by the Owner and/or the City of Dallas.
- Concrete for all concrete pavement and curbs shall be Class "Machine Finish" 4000 PSI of Class "Hand Finished" 4500 PSI per City of Dallas Department of Public Works Addendum to North Central Texas Standard Specifications for Public Works Construction (October, 2011).
- Concrete paving joints shall be constructed as recommended in the geotechnical report noted below. Expansion joints shall be placed at changes in direction of paving, at driveways and/or as shown on the drawings. Seal all joints as shown on the drawings.
- Paving sections shall be sawcut in 15' x15' squares.
- Site grading and pavement subgrade shall be prepared in accordance with the Geotechnical Report No.19:6529 prepared by ECS Texas, LLP. dated April 24, 2015.
- Unless otherwise indicated on plans, all dimensions are to face of curb or face of building and are perpendicular to property line. These dimensions are provided to tie the Architect's Site Plan to the property lines.
- All sidewalks and handicap parking areas shall meet current ADA standards for minimum and maximum slopes.

PRIVATE WATER AND SANITARY SEWER NOTES:

- 1. All materials and workmanship for private utility construction shall conform to the Standard Specifications for Public Works Construction for North Central Texas, latest edition, and the City of Dallas requirements.
- Pipe material for water lines shall conform to the notes shown on this drawing and to requirements of the project specifications. Water line for fire service shall be C900 PVC, DR 14 Class 200, Water lines for domestic use shall be Type 'K' Copper from tap to meter and copper or AWWA C900 PVC.
- 3. All bends and tees in water mains shall have thrust blocking provided in accordance with City of Dallas standard
- 4. No water jetting shall be allowed.
- All sanitary sewer pipe 12" and smaller shall be PVC SDR 35 pipe, solid wall, in compliance with ASTM D 3034, latest revision. All pipe joints shall be in compliance with ASTM D 3212, latest, revision. Other pipe material shall be subject to approval by the City Engineer.
- Water mains shall have the following minimum cover below street grades:

i.	Size	Cover
i.	6"	3.5'
i.	8"	4.0'
<i>'</i> .	10"	4.0'
<i>'</i> .	12"	5.0'
i.	>16"	6.0'

- 7. Coordinate utility service locations with most current Architectural/MEP Plans for this project. Notify Engineer with any discrepancies.
- Fire service shall be sized and designed by a State of Texas licensed fire protection engineer/contractor registered in the State of Texas.
- 9. Fire hydrants must be located 1.5 feet to 3-feet from the edge of the fire lane.
- All underground fire lines shall be installed by a state licensed fire protection contractor.
- 11. Refer to City of Dallas standard details for DDC valve and vault construction, Water and Sanitary Sewer embedment and water thrust blocking.
- 12. Field adjustments shall not be made without notification of the Owner and engineer.
- Utility service locations shall be plugged 5' from future building. Refer to Architectural /MEP Plans for this project for future continuation of building utilities.
- All water and sanitary sewer services shall be tested as required by the City of Dallas. Paving shall not take place until utilities are tested and accepted by the City of Dallas.

NOTE:

In addition to the Building Permits, a Right-of-Way Permit and Traffic Control Approval must be applied for and approved prior to any work within the Right-of-Way.

> * **B. DAVID LITTLETON** 62128 THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY B. DAVID LITTLETON, P.E. #62128 ON 04-27-2016. ALTERATION OF A SEALED

DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE

THE RESPONSIBLE ENGINEER IS AN OFFENSE
UNDER THE TEXAS ENGINEERING PRACTICE ACT.
THE RECORD COPY OF THIS DRAWING IS ON FILE
AT THE OFFICES OF HALFF ASSOCIATES, INC.
1201 NORTH BOWSER ROAD, RICHARDSON

TEXAS 75081 TBPE FIRM #F-312

Project No.: 30735

Drawn By: CAD

Checked By: KM / BDL

NOVEMBER, 2016

AS SHOWN

GENERAL NOTES

WER

STRE

OF

DWU BENCHMARK : "X" CUT ON CONCRETE CURB CENTER OF STORM SEWER INLET AT THE SOUTHEAST CORTNER OF ALAMO ST. AND CEDAR SPRINGS RD. NORTHING 6974860.151 EASTING 2489331.029


CONTROL POINT #100: SET IRON ROD TRAVERSE POINT IN THE MEDIAN OF PEARL ST. LOCATED APPROX. 40LF NE OF A CURB INLET ON THE SW SIDE OF PEARL ST. NORTHING 6975411.25 EASTING 2491377.38 ELEVATION 454.47 feet

ELEVATION 418.87 feet

C0.01 CITY OF DALLAS 311T-8854

Scale:

Sheet Title



and across said Olive Street along the northwesterly line of said "Tract IV", a

found on said northeasterly right-of-way line of Olive Street, same being the

THENCE South 49 degrees 14 minutes 09 seconds East, along said

northeasterly right-of-way line of Olive Street, same being the common

a distance of 196.02 feet to the POINT OF BEGINNING AND CONTAINING

northeasterly line of said "Tract IV" and southwesterly line of said "Tract II",

2.352 square feet or 0.0540 acres of land, more or less.

westerly corner of said "Tract II";

distance of 12.00 feet to a 5/8 inch iron rod with cap stamped "SURVCON"

an "X" cut set for corner:

THENCE North 49 degrees 14 minutes 09 seconds West, continuing over and across

said Flora Street along the southeasterly line of said "Tract III", a distance of 16.37 feet to

THENCE North 40 degrees 45 minutes 51 seconds East, continuing over and across said

Flora Street along the southwesterly line of said "Tract III", a distance of 12.00 feet to the

POINT OF BEGINNING AND CONTAINING 11,458 square feet or 0.2630 acres of land,

P.K. nail with aluminum shiner stamped "HALFF" set for corner;

PARKING NOTES

REGULAR SPACES: 139

HANDICAP SPACES: 6

TOTAL SPACES: 145

TRAFFIC SIGN

GROUND LIGHT

1/2-INCH FOUND IRON ROD

CONTROL MONUMENT

REF. P.O.L. REFERENCE POINT ON LINE

1/2-INCH SET IRON ROD WITH YELLOW

P.K. NAIL SET WITH SHINER STAMPED "HALFF"


PLASTIC CAP STAMPED "HALFF"

1/2" FIR


1/2" SIR

W/CAP

(C.M.)



LOCATION MAP NOT TO SCALE



LEGAL DESCRIPTION - "TRACT II"

BEING a 44,988 square feet tract of land situated in the John Grigsby Survey, Abstract No. 495, Dallas County, Texas and being part of City of Dallas Block 528, and being part of Lots 1, 2, 3, 9, 10 and 13 of Hensley Addition, an addition to the City of Dallas as recorded in Volume 90, Pages 274 and 275 of the Deed Records of Dallas County, Texas (D.R.D.C.T.), said tract Iso being part of that tract of land described as "Tract No. 1", and being an a portion of "Old Pearl Street-Munger Ave (formerly Juliette Street)" as described in City of Dallas Ordinance 17633, as recorded in Volume 82250, Page 1383, D.R.D.C.T., and being all of that tract of land described as "Tract II" in Special Warranty Deed to Arts District Properties, LTD., (hereinafter referred to as "Tract II"), as recorded in Volume 98103, Page 00066, D.R.D.C.T., and being more particularly described by metes and bounds as follows:

BEGINNING at a 5/8 inch iron rod with cap stamped "SURVCON" found for corner at the south westerly end of a corner clip at the intersection of the northwesterly right-of-way line of Flora Street (a variable width public right-of-way) with the northeasterly right-of-way line of Olive Street (a variable width public right-of-way), said iron rod also being a southerly corner of said "Tract II" and the northeasterly corner of that tract of land described as "Tract IV", and an angle point in the northwesterly line of that tract of land described as "Tract III" in the aforementioned deed to Arts District Properties, LTD.;

THENCE North 49 degrees 14 minutes 09 seconds West, along said northeasterly right-of-way line of Olive Street, same being the common southwesterly line of said "Tract II" and northeasterly line of said "Tract IV", a distance of 196.01 feet to a 5/8 inch iron rod with cap stamped "SURVCON" found for the intersection of said common line with the southeasterly line of that tract of land as described in District Court Agreed Judgment Number 83-2891-D to the State of Texas and the City of Dallas, as recorded in Volume 84020, Page 3789, D.R.D.C.T. (hereinafter referred to as "Olive Loop" tract), said corner also being the beginning a non-tangent circular curve to the left, having a radius of 130.00 feet and whose chord bears North 65 degrees 19 minutes 30 seconds East, a distance of 90.28 feet, from which point a 1/2-inch iron rod found for witness on the southeasterly line of that tract of land described as "Tract No. 1" for the abandonment of "Old Pearl Street-Munger Ave." bears North 46 degrees 01 minutes 14 seconds West, a distance of 5.00 feet;

THENCE Northeasterly, departing said northeasterly right-of-way line and along the common northwesterly line of said "Tract II" and southeasterly line of said "Olive Loop" tract, and along said circular curve to the left, through a central angle of 40 degrees 38 minutes 10 seconds and an arc distance of 92.20 feet to a 1/2-inch iron rod with a yellow plastic cap stamped "HALFF"

distance of 16.35 feet to a 5/8-inch iron rod found for corner, said point being the point of curvature of a tangent circular curve to the left, having a radius of 190.00 feet and whose chord bears North 25 degrees 27 minutes 48 seconds East, a distance of 127.11 feet;

left, through a central angle of 39 degrees 05 minutes 03 seconds and an arc distance of 129.61 feet to a 5/8-inch iron rod with cap stamped "SURVCON" for a corner; THENCE North 63 degrees 37 minutes 08 seconds East, continuing along said common line, a

distance of 36.17 feet to a P.K. nail w/ aluminum shiner stamped "HALFF" (hereinafter referred to as "P.K. nail set") set for corner on the southwesterly right-of-way line of the Pearl Street (a variable width right-of-way, also known as "Pearl Street Ramp" and "State Highway

THENCE South 46 degrees 45 minutes 00 seconds East, along the common northeasterly line of said "Tract II" and southwesterly line of said "Olive Loop" tract, same being said southwesterly right-of-way line of Pearl Street, a distance of 60.72 feet to a point (not monumented) on a concrete curb stop for corner, from which a P.K. nail set on line for witness bears South 51 degrees 22 minutes 13 seconds East, a distance of 2.00 feet;

THENCE South 51 degrees 22 minutes 13 seconds East, continuing along said common line, passing at a distance of 2.00 feet the aforementioned P.K. nail set on line for witness, and continuing a total distance of 76.10 feet to a "Y" cut set in concrete for corner;

THENCE South 39 degrees 19 minutes 54 seconds East, continuing along said common line, a distance of 57.00 feet to a point for corner at the intersection of said common line with said northwesterly right-of-way line Flora Street, from which an "X" cut found for witness bears North 78 degrees 51 minutes 22 seconds East, a distance of 0.23 feet, said point for corner also being the easterly corner of said "Tract II" and the northerly corner of said "Tract III";

THENCE South 44 degrees 16 minutes 32 seconds West, along the common southeasterly line of said "Tract II" and northeasterly line of said "Tract III", same being said northwesterly right-of-way line of Flora Street, a distance of 242.74 feet to a 5/8-inch iron rod with cap stamped "SURVCON" for the northeasterly corner of the aforementioned corner clip at the intersection of said common line with the northeasterly right-of-way line of Olive Street;

THENCE South 67 degrees 07 minutes 16 seconds West, continuing along said common line and along said corner clip, a distance of 2.75 feet to the POINT OF BEGINNING AND CONTAINING 44,988 square feet or 1.0328 acres of land, more or less.

PROPERTI


DISTRIC⁻

Project No.: 29307 03 / 29 / 2013 Drawn By: JLM Checked By: CJH Scale: ·1"=30'

ALTA/ACSM LAND TITLE SURVEY

1 of 2 Sheet Number

Sheet Title



LINE DATA TABLE						
NO.	BEARING	DISTANCE				
L1	N49*39′51"W	61.87′				
L2	S47°31′19"E	55 . 25′				
L3	N47°31′19°W	55 . 25′				
4	S47°31′19°E	41.32′				
L 5	N47°31′19"W	41.80′				
L6	N75*34'28 "W	1.00′				
L7	S49*39′51*E	52 . 66′				
	NO. L1 L2 L3 L4 L5	NO. BEARING L1 N49*39'51"W L2 S47*31'19"E L3 N47*31'19"W L4 S47*31'19"E L5 N47*31'19"W L6 N75*34'28"W	L1 N49*39′51"W 61.87′ L2 S47*31′19"E 55.25′ L3 N47*31′19"W 55.25′ L4 S47*31′19"E 41.32′ L5 N47*31′19"W 41.80′ L6 N75*34′28"W 1.00′			

			CURVE TA	ABLE		
NO.	DELTA	RADIUS	TANGENT	LENGTH	CHORD LENGTH	CHORD BEARING
C1	07*04′18*	89.00′	5 . 50′	10.98′	10.98′	S81°16′31"E
C2	02*00′46"	130.00′	2.28′	4.57′	4.57′	S76°27′25"W
С3	45°44′14"	89.00′	37 . 54′	71.05′	69.17′	N72*19"12"E
C4	28*13′47"	130.00′	32.69′	64.05′	63.41′	S61*20'09*W
C5	24*51′40"	190.00′	41.88′	82.44′	81.80′	S20*52'51"W
C6	16*20′21*	149.00′	21.39′	42.49′	42.35′	N22*35′42"E
C7	16*46'29"	148.00′	21.82′	43.33'	43.18′	N06°02′16"E

LEGEND:

POB POINT OF BEGINNING POC POINT OF COMMENCING

REF. P.O.L. REFERENCE POINT ON LINE P.K. SET W/SHINER P.K. NAIL SET WITH SHINER STAMPED "HALFF"

1/2-INCH FOUND IRON ROD 1/2" FIR 1/2-INCH SET IRON ROD WITH YELLOW 1/2" SIR PLASTIC CAP STAMPED "HALFF" W/CAP

CONTROL MONUMENT

The Surveyor has reviewed Schedule B of First American Title Insurance Company's Title Commitment GF No. 1002-43179-RTT, with an effective date of March 11, 2013, issued March 27, 2013, wherein subject tracts are described as "Tract II, III, IV and V". The following exceptions listed therein affect or do not affect the subject tracts as noted below. All recording information listed below references the County Clerk Records of Dallas County, Texas.

Terms, provisions, conditions, and easements contained in City of Dallas Ordinance No. 18028, recorded in Volume 84020, Page 3704, D.R.D.C.T., as amended by Ordinance No. 18098, recorded in Volume 84020, Page 3734, D.R.D.C.T. (Affects "Tracts III and IV" as shown hereon, Schedule B, Item 10 (d))

Terms, provisions, conditions, and easements contained in Agreed Judgment in Case No. 83-2891-D, recorded in Volume 84020, Page 3739, D.R.D.C.T. (does not affect, as shown hereon, Schedule B, Item 10 (e)

Sidewalk and Drainage Easement to the City of Dallas recorded in Volume 85069, Page 2967, D.R.D.C.T. (Affects "Tract II" as shown hereon, Schedule B, Item

Terms, provisions, conditions, and easements contained in City of Dallas Ordinance No. 17633, recorded in Volume 82250, Page 1383, D.R.D.C.T. (Affects "Tract II" as shown hereon, Schedule B, Item 10 (g)

Terms, provisions, and conditions of Declaration of Covenants recorded in Volume 98103, Page 89, D.R.D.C.T. Affected by County Clerk's File No. 201000150980, D.R.D.C.T. (Affects "Tracts II, III, and IV", Schedule B, Item 10 (h)

Terms, provisions, conditions, and easements contained in Development and Easement Agreement recorded in County Clerk's File No. 201000150980, O.P.R.D.C.T. (Affects "Tract II" as to 481 SF "Museum Tower Support Easement Area" and 1,116 SF "Museum Tower Access Easement Area" as shown hereon, Schedule B Item 10 (i)) .

Terms, provisions, and conditions of Agreement, recorded in Volume 84020, Page 3811, D.R.D.C.T. (does affect Tract V, as shown on survey, schedule b, item

Terms, provisions, and conditions of Ordinance No. 17633, recorded in Volume 82250, Page 1383, D.R.D.C.T. (does affect Tract V, as shown on survey, schedule b, item

Terms, provisions, and conditions of Agreed Judgment, recorded in Volume 84020, Page 3739, D.R.D.C.T. (does affect Tract V, as shown on survey, schedule b, item 10 (m)) .

Dallas, as recorded in Volume 84020, Page 3789 of the Deed Records of Dallas County, Texas (D.R.D.C.T.) (hereinafter referred to as "Olive Loop" tract) with the northwesterly line of that tract of land described as "Tract II" in Special Warranty Deed to Arts District Properties, Ltd., as recorded in Volume 98103, Page 66, D.R.D.C.T., said corner also being the beginning a non-tangent circular curve to the left having a radius of 190.00 feet, whose chord bears South 07 degrees 11 minutes 09 seconds West, a distance of 8.39 feet:

VOL. 98103, PG. 66

D.R.D.C.T.

1. The Basis of Bearing is the Texas Coordinate System of 1983, North Central Zone

2. By graphical plotting, the Property is located in Zone "X," on the Dallas County,

(4202) as derived from the Texas Department of Transportation (T.X.D.O.T.)

Texas and Incorporated Areas Flood Insurance Rate Map, Map Number

48113C0345J, dated August 23, 2001, for the Federal Emergency Management

Agency. Zone "X" is defined as "Areas determined to be outside the 0.2% annual

chance floodplain." The Surveyor utilized the above referenced flood plain

information for this determination and the Surveyor does not certify that revised

flood plain information has or has not been published by the Federal Emergency

To: Flora Street Lofts, LTD., Arts District Properties, LTD. and First American Title

This is to certify that this map or plat and the survey on which it is based were

made in accordance with the 2011 Minimum Standard Detail Requirements for

ALTA/ACSM Land Title Surveys, jointly established and adopted by ALTA and

NSPS, and includes Items 1-4, 7 (a) , 7 (b) (1) , 7 (c) , 8, 9, 11 (a) , and 13

of Table A thereof. The field work was completed on February 27, 2013.

GENERAL NOTES

control network.

Management Agency or some other source.

REGISTERED PROFESSIONAL LAND SURVEYOR

SURVEYOR'S CERTIFICATE

Date of Map: March 28, 2013

Insurance Company:

JOÉL C. HOWARD

TEXAS NO. 6267

THENCE Southwesterly, along the common southeasterly line of said "Olive Loop" tract and said northwesterly line of said "Tract II" and along said curve, through a central angle of 02 degrees 31 minutes 46 seconds, an arc distance of 8.39 feet to a point (not monumented) for the POINT OF BEGINNING of the herein described tract, and for the beginning of a non-tangent circular curve to the right having a radius of 190.00 feet, whose chord bears South 20 degrees 52 minutes 51 seconds West, a distance of 81.80 feet:

THENCE Southwesterly, continuing along said common line and along said curve, through a central angle of 24 degrees 51 minutes 40 seconds, an arc distance of 82.44 feet to a point (not monumented) for corner;


THENCE North 47 degrees 31 minutes 19 seconds West, departing said common line and over and across said "Olive Loop" tract, a distance of 41.80 feet to a point (not monumented) for the beginning of a non-tangent circular curve to the left having a radius of 149.00 feet. whose chord bears North 22 degrees 35 minutes 42 seconds East, a distance of 42.35 feet, said corner being on the common southwesterly line of "Museum Tower, A Condominium" as recorded in instrument Number 20070418077, O.P.R.D.C.T. and northwesterly line of said "Olive Loop"

THENCE Northeasterly, along said common line and along said curve, through a central angle of 16 degrees 20 minutes 21 seconds, an arc distance of 42.49 feet to an "X"-cut found for corner;

THENCE North 75 degrees 34 minutes 28 seconds West, continuing along said common line, a distance of 1.00 feet to an "X"-cut found for the beginning of a non-tangent circular curve to the left having a radius of 148.00 feet, whose chord bears North 06 degrees 02 minutes 16 seconds East, a distance of 43.18 feet;

THENCE Northeasterly, continuing along said common line and along said curve, through a central angle of 16 degrees 46 minutes 29 seconds, an arc distance of 43.33 feet to a point (not monumented) for corner;;

THENCE South 49 degrees 39 minutes 51 seconds East, departing said common line and over and across said "Olive Loop" tract, a distance of 52.66 feet to the POINT OF BEGINNING AND CONTAINING 3.474 square feet or 0.08 acres of land, more or less.



SCALE: 1"=30"

LEGAL DESCRIPTION - TRACT V - PARCEL A AIR RIGHTS AND SUBSURFACE RIGHTS

BEING a 0.063 tract of land situated in the John Grigsby Survey, Abstract No. 495 Dallas County, Texas and being part of City of Dallas Block 528, and being all of that called 2.730 square foot (0.063 acres) tract of land described in Special Warranty Deed to Arts District Properties, Ltd. recorded in Instrument Number 201300088466 of the Official Public Records of Dallas County, Texas (O.P.R.D.C.T.) and being more particularly described as follows:

COMMENCING at a 5/8-inch iron rod with cap stamped "SURVCON" found for the intersection of the northeasterly line of Olive Street (a variable width right-of-way) with the southeasterly line of that tract of land as described in District Court Agreed Judgment Number 83-2891-D to the State of Texas and the City of Dallas, as recorded in Volume 84020, Page 3789 of the Deed Records of Dallas County, Texas (D.R.D.C.T.) (hereinafter referred to as "Olive Loop" tract), said corner also being the beginning a non-tangent circular curve to the left having a radius of 130.00 feet, whose chord bears North 80 degrees 32 minutes 48 seconds East, a distance of 22.78 feet, said corner also being the westernmost corner of that tract of land described as "Tract II" in Special Warranty Deed to Arts District Properties, Ltd., as recorded in Volume 98103, Page 66, D.R.D.C.T.;

THENCE Northeasterly, along the common southeasterly line of said "Olive Loop" tract and northwesterly line of said "Tract II" and along said curve, through a central angle of 10 degrees 11 minutes 32 seconds, an arc distance of 23.13 feet to a point (not monumented) for the POINT OF BEGINNING of the herein described

THENCE North 47 degrees 31 minutes 19 seconds West, departing said common line and over and across said "Olive Loop" tract, a distance of 55.25 feet to a point (not monumented) for the beginning of a non-tangent circular curve to the left having a radius of 89.00 feet, whose chord bears North 72 degrees 19 minutes 12 seconds East, a distance of 69.17 feet, said corner being on the common northwesterly line of said "Olive Loop" tract and southeasterly line of the "Museum Tower, A Condominium" as recorded in instrument Number 20070418077, O.P.R.D.C.T.:

THENCE Northeasterly, along said common line and along said curve, through a central angle of 45 degrees 44 minutes 14 seconds, an arc distance of 71.05 feet to a point (not monumented) for corner:

THENCE South 47 degrees 31 minutes 19 seconds East, departing said common line and over and across said "Olive Loop" tract, a distance of 41.32 feet to a point not monumented) for the beginning of a non-tangent circular curve to the right having a radius of 130.00 feet, whose chord bears South 61 degrees 20 minutes 09 seconds West, a distance of 63.41 feet, said corner being on said common southeasterly line of said "Olive Loop" tract and northwesterly line of said "Tract II";

THENCE Southwesterly, along said common line and along said curve, through a central angle of 28 degrees 13 minutes 47 seconds, an arc distance of 64.05 feet to the POINT OF BEGINNING AND CONTAINING 2,738 square feet or 0.0629 acres of land, more or less.

LEGAL DESCRIPTION - TRACT V - PARCEL B AIR RIGHTS AND SUBSURFACE RIGHTS

BEING a 0.006 tract of land situated in the John Grigsby Survey, Abstract No. 495, Dallas County, Texas and being part of City of Dallas Block 528, and being all of that called 281 square foot (0.006 acres) tract of land described as "Tract 1" in Special Warranty Deed to Arts District Properties, Ltd. recorded in Instrument Number 201300088468 of the Official Public Records of Dallas County, Texas (O.P.R.D.C.T.) and being more particularly described as follows:

COMMENCING at a 5/8-inch iron rod with cap stamped "SURVCON" found for the intersection of the northeasterly line of Olive Street (a variable width right-of-way) with the southeasterly line of that tract of land as described in District Court Agreed Judgment Number 83-2891-D to the State of Texas and the City of Dallas, as recorded in Volume 84020, Page 3789 of the Deed Records of Dallas County, Texas (D.R.D.C.T.) (hereinafter referred to as "Olive Loop" tract), said corner also being the beginning a non-tangent circular curve to the left having a radius of 130.00 feet, whose chord bears North 81 degrees 33 minutes 11 seconds East, a distance of 18.54 feet, said corner also being the westernmost corner of that tract of land described as "Tract II" in Special Warranty Deed to Arts District Properties, Ltd., as recorded in Volume 98103, Page 66, D.R.D.C.T.;

THENCE Northeasterly, along the common southeasterly line of said "Olive Loop" tract and northwesterly line of said "Tract II" and along said curve, through a central angle of 08 degrees 10 minutes 46 seconds, an arc distance of 18.56 feet to a point (not monumented) for the POINT OF BEGINNING of the herein described

THENCE North 49 degrees 39 minutes 51 seconds West, departing said common line and over and across said "Olive Loop" tract, a distance of 61.87 feet to an "X"-cut found for the beginning of a non-tangent circular curve to the left having a radius of 89.00 feet, whose chord bears South 81 degrees 16 minutes 31 seconds East, a distance of 10.98 feet, said corner also being the southernmost corner of the "Museum Tower, A Condominium" as recorded in instrument Number 20070418077, O.P.R.D.C.T.;

THENCE Northeasterly, along the common northwesterly line of said "Olive Loop" tract and southeasterly line of said "Museum Tower, A Condominium" and along said curve, through a central angle of 07 degrees 04 minutes 18 seconds, an arc distance of 10.98 feet to a point (not monumented) for corner;

THENCE South 47 degrees 31 minutes 19 seconds East, departing said common line and over and across said "Olive Loop" tract, a distance of 55.25 feet to a point (not monumented) for the beginning of a non-tangent circular curve to the right having a radius of 130.00 feet, whose chord bears South 76 degrees 27 minutes 25 seconds West, a distance of 4.57 feet, said corner being on said common southeasterly line of said "Olive Loop" tract and northwesterly line of said "Tract II";

THENCE Westerly, along said common line and along said curve, through a central angle of 02 degrees 00 minutes 46 seconds, an arc distance of 4.57 feet to the POINT OF BEGINNING AND CONTAINING 281 square feet or 0.006 acres of land, more or less.


S

OPE PR

R

S

 \simeq




Project No.: 29307

03 / 29/ 2013 Issued: Drawn By: JLM Checked Bv: CJH Scale: ·1"=30'

> ALTA/ACSM LAND TITLE SURVEY


Sheet Title


2 of 2





THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY B. DAVID LITTLETON, P.E. #62128 ON 04-27-2016. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT. THE RECORD COPY OF THIS DRAWING IS ON FILE AT THE OFFICES OF HALFF ASSOCIATES, INC. 1201 NORTH BOWSER ROAD, RICHARDSON TEXAS 75081 TBPE FIRM #F-312

AUGUST, 2015













NOVEMBER, 2016


AS SHOWN






























Erosion Control Notes

- 1. The Contractor is responsible for implementing a Storm Water Pollution Prevention Plan (SWP3) in accordance with TCEQ Texas Pollutant Discharge Elimination System (TPDES) Permit No. TXR150000 (PERMIT). The details shown on this sheet represent typical methods for controlling erosion during construction and are intended for the Contractors guidance in the implementation of the Pollution Prevention Plan. The plan shall comply with the PERMIT and Federal, State and local requirements. The plan shall include, but not be limited to, preparation and submittal of a Notice of Intent (NOI) to the TCEQ, if the project is 5 acres or larger and preparation of all plans and documentation as required by the PERMIT.
- 2. It is the intent of the information provided on these documents to be used as a general guideline for the Contractor. The SWP3 to be prepared shall meet the current requirements set forth in the TCEO's TPDES generalpermit for storm water discharges from construction sites as well as any local requirements.
- 3. The Contractor shall be responsible for maintaining erosion control during construction and for obtaining any required construction related drainage permits, or making any construction related notifications. An inspection report that summarizes inspection activities and implementation of the SWP3 shall be performed as required by the PERMIT and retained by the Contractor and made a part of the construction documents. The Contractor shall provide copies of all SWP3 documents including, but not limited to, inspection records, original plans, and modified plans to the Owner at contract close-out. During construction the contractor shall provide copies of the inspection reports to the Owner on a monthly basis.
- 4. Temporary storm drainage and/or erosion controlmaterial shall be suitable for this application and shall be installed with the proper techniques by the Contractor as required by NCTCOG Standard Specifications for Public Works Construction. Temporary storm drainage and/or erosion controlmaterial shall be removed by the Contractor, in addition to any excavations backfilled by the Contractor, in accordance with NCTCOG Standard Specifications for Public Works Construction when temporary erosion control devices are no longer needed as specified in the PERMIT. Maintenance of the permanent erosion controlmeasures at the site will be assumed by the Owner at contract close out and acceptance of the work.
- 5. The Contractor shall maintain the SWP3 in accordance with the TCEQ Permit and make the SWP3 available, upon request, to the TCEQ and/or Owner.
- 6. The Contractor must amend the SWP3 whenever there is a change in design, construction, operation, or maintenance of the SWP3, or when the existing SWP3 proves ineffective. Modifications shall not compromise the intent of the requirements of the PERMIT. Modifications including design and all additional materials and work shall be accomplished by the Contractor at no additional expense to the Owner.
- 7. The Contractor shall inspect his stabilization and erosion controlmeasures at a minimum of once every 14 days, and within 24 hours after any storm event greater than 0.5 inches, or once every 7 days. The Contractor shall repair inadequacies revealed by the inspection before the next storm event and he shall modify his SWP3 within 7 days of the inspection.
- 8. The Contractor shall adopt and implement appropriate construction site management practices to prevent the discharge of oils, grease, paints, gasoline, and other pollutants to storm water. Appropriate practices shall include, but not be limited to: designating areas for equipment maintenance and repair; collecting wastes periodically; maintaining conveniently located waste receptacles, and designating and controlling equipment washdown.
- 9. Borrow areas, if excavated, shall be protected and stabilized by the Contractor in a manner acceptable to the Owner and in accordance with PERMIT requirements.
- 10. All non-paved areas shall be seeded and mulched with erosion protection grass by the Contractor immediately upon completion of final grading. This includes all ditches and embankments. The Contractor shall maintain final grading. and keep seeded areas watered until fully established and accepted by Owner.
- 11. The Contractor shall construct a slit fence at locations suggested on plans as appropriate or as modified in his SWP3 to fit site conditions at the time of placement, and all borrow and stock pile areas. The silt fence shall be constructed as detailed on this plan. The Contractor shall remove accumulated silt when it reaches a depth of 1/3 the height of the silt fence. The Contractor shall dispose of the removed silt in a location approved by the Owner and in such a manner as to not contribute to erosion and sedimentation. The Contractor shall remove the silt fence when the site is completely stabilized in accordance with the PERMIT.
- 12. The Contractor shall designate material and equipment storage areas mutually agreed to by the Owner. The storage areas shall be graded for positive drainage, and the surface stabilized with a minimum of 2 inches of compacted flex base on 6 inches of scarified and recompacted subgrade by the Contractor. A silt fence shall be installed by the Contractor around the storage areas to prevent eroded material from leaving the site.
- 13. All inlets (onsite and offsite) receiving drainage water from disturbed areas shall be protected by the Contractor as per details shown or other Owner approved methods to prevent eroded material from being transported into inlets. The inlet protection shall be constructed as shown on these plans.
- 14. The notes and details contained herin do not relieve the Contractor and Owner of meeting and implementing the requirements of the PERMIT.





SILT FENCE

N.T.S.

SILT FENCE GENERAL NOTES:

- 1. STEEL POSTS WHICH SUPPORT THE SILT FENCE SHALL BE INSTALLED WITH A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF TWO FEET.
- 2. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (e.g. PAVEMENT), WEIGHT FABRIC FLAP WITH WASHED GRAVEL ON UPHILL SIDE TO PREVENT FLOW UNDER FENCE.
- 3. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.
- 4. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHALL BE A 6'DOUBLE OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.
- 5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL. REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
- 6. SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.
- 7. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 6 INCHES. THE SILT SHALL BE DISPOSED OF IN AN APPROVED SITE AND IN SUCH A MANNER AS TO NOT CONTRIBUTE TO ADDITIONAL SILTATION.






ISOMETRIC VIEW

ROCK CHECK DAM


ROCK CHECK DAM GENERAL NOTES:


- 1. WOVEN WIRE SHEATHING SHALL HAVE MAXIMUM OPENING OF ONE (1)
 INCH AND A MINIMUM WIRE SIZE OF 20 GAUGE AND SHALL BE SECURED
 WITH SHOAT RINGS.
- 2. THE ROCK BERM SHALL BE INSPECTED WEEKLY OR AFTER EACH RAIN AND SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION PROPERLY.
- 3. WHEN SILT REACHES A DEPTH EQUAL TO ONE-THIRD OF THE HEIGHT OF THE BERM OR ONE FOOT, WHICHEVER IS LESS, THE SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.
- 4. WHEN THE SITE IS COMPLETELY STABILIZED, THE BERM AND ACCUMULATED SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.




PLAN VIEW

TEMPORARY CONSTRUCTION ENTRANCE DETAIL N.T.S.









CONCRETE BLOCK FILTER NOTE: GRAVEL FILTERS MAY BE USED ON PAVEMENT OR BARE GROUND


> GRATE INLET FILTER PROTECTION




SILT FENCE DROP



FILTER FABRIC CURB INLET PROTECTION N.T.S.







COMBINATION CURB INLET FILTER PROTECTION

N.T.S.

CITY OF DALLAS 311T-8854





THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY B. DAVID LITTLETON, P.E. #62128 ON 04-27-2016. ALTERATION OF A SEALED ON 04-27-2016. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT. THE RECORD COPY OF THIS DRAWING IS ON FILE AT THE OFFICES OF HALFF ASSOCIATES, INC. 1201 NORTH BOWSER ROAD, RICHARDSON TEXAS 75081


TBPE FIRM #F-312


Project No.: 30735 MARCH, 2016 Issued: Drawn By: CAD Checked By: KM / BDL


AS SHOWN Scale: Sheet Title **EROSION CONTROL** NOTES & DETAILS


C6.02

THIS IS NOT A STORM WATER POLLUTION PREVENTION PLAN. THE CONTRACTOR MUST PREPARE ALL RELEVANT DOCUMENTS INCLUDING HIS OPERATION SPECIFIC INFORMATION PER THE TCEQ TPDES PERMIT NO. TXR150000. INCLUDING ALL DOCUMENTATION & CERTIFICATIONS AS REQUIRED BY THE PERMIT.












PLAN






GRANITE FILL COVER








NOTE: CENTER LINE OF 8" SQUARE PAVERS ABOVE AND BELOW JOINTS TO BE SYMMETRICAL AND SQUARE ABOUT THE JOINT CENTER LINE.

JOINT SPACING SHALL VARY BETWEEN 3/2" MINIMUM TO 5/8" MAXIMUM AS FIELD CONDITIONS WARRANT.

PLAN REVISION						
NO.	DESCRIPTION	EY.	DATE			
3	ADD BACKFLOW PREVENTIER VAULT SIZE TO DETAIL	PW	4-1-88			



DAL	LAS	ARTS	DISTRICT
		COTI	MUTC

Pavement Details

	YTI	OF	DAL	LAS.	TEXA	IS
NON	DRAWN	DATE	SCALE	MOTES	PM.8	A40

E219N	DRAWN	DATE	SCALE	NOTES	PILE	MQ.
RT/No	41/21	7.17.87	AS NOTED		3110	3133

T

